

SECTION 009113 – ADDENDUM

PART 1 - Addendum 2

1.1 PROJECT INFORMATION

- A. Project Name: Riverview Gardens High School Building 9.
- B. Owner: Riverview Gardens School District.
- C. Date of Addendum: 04/30/2020.

1.2 NOTICE TO BIDDERS

- A. This Addendum is issued to all registered plan holders pursuant to the Instructions to Bidders and Conditions of the Contract. This Addendum serves to clarify, revise, and supersede information in the Project Manual, Drawings, and previously issued Addenda. Portions of the Addendum affecting the Contract Documents will be incorporated into the Contract by enumeration of the Addendum in the Owner/Contractor Agreement.
- B. The second sheet of Addendum 1 shall be discarded.
- C. The Bidder shall acknowledge receipt of this Addendum in the appropriate space on the Bid Form.
- D. The date for receipt of bids has changed by this Addendum, at **10 am May 12, 2020**; same location.

1.3 ADDITIONAL INFORMATION FOR SCOPE OF WORK

- A. Install all new electrical wires to all 3 security cameras mounted at the roof level.
 - 1. All new wire shall be installed through rigid conduit and ensure current code is followed.
- B. All cables currently running through the roof hatch shall be re-routed through a new penetration through the concrete deck and appropriately spaced away from the roof hatch.
 - 1. Electricians are not responsible for core drilling the hole in the concrete. This will be the responsibility of the roofing contractor.
- C. Roofing contractors can lift all other cables to install new roofing underneath. These cables on the roof top are to be re-bundled after the roof has been installed.
 - 1. If any cables can be removed, they will be appropriately marked.
 - 2. Electrical contractors to be responsible for grouping the cables and removing any cables marked for removal.
 - 3. Roofing contractor to supply the new wood blocking for the cables.
- D. The three skylights currently on the roof top are to all be eliminated as part of the roofing project. Properly secure and cover the holes prior to the application of new roofing material.

Riverview Gardens School District

Building 9 replacement

E. Attached is sign in sheets

END OF SECTION 009113